



**BUREAU
VERITAS**

Type Certificate

Applicant: REFU Elektronik GmbH
Address: Marktstrasse 185,
 72793 Pfullingen,
 Germany

Type of power generating unit:	Grid-tied photovoltaic inverter	REFUsoI 50K-3T	REFUsoI 60K-3T	REFUsoI 70K-3T
Technical data:	Nominal active output power:	50 kW	60 kW	70 kW
	Max. apparent power:	50 kVA	60 kVA	75 kVA
	Nominal output AC voltage:	400 V (3~ + N + PE)		480 V (3~ + PE)
	Nominal frequency:	50 Hz		
Technical data determined by measurements:	Max. active power $P_{E_{max}}$ / Max. active power peak $P_{600}^{1)}$:	--- ¹⁾	60,00 kW	70,07 kW
Software version:	V2.00 or higher			

Validated type model:	Model file:	REFU_21-0004_0_TR4_REFUsoI 50-70K-3T_V1_V1.zip
	Identification number (MD5):	d068bc57dd75800939353ba09f07ce7b

Grid connection regulation: **VDE-AR-N 4110:2018-11** – Technical requirements for the connection and operation of customer installations to the medium voltage network (TCR medium voltage) [1]

Pertinent standards / Guidelines: Technical guidelines:
 FGW TR 3 Rev. 25 [3], FGW TR 4 Rev. 09 [4], FGW TR 8 Rev. 09 [5]

The power generating units, stated in the certificate, were tested and certified according to the technical guidelines referenced to the grid connection regulation. The electrical characteristics fulfil the requirements of the grid connection regulation:

- Quasi-steady-state operation
- Dynamic network stability (reactive current characteristic according to TCR medium voltage)
- Active power output and network security management
- Active power adjustment as a function of the grid frequency
- Protection technology and protection settings on generating unit level
- Power quality

The manufacturer has provided proof of certification of the quality management system of his production facility in accordance with ISO 9001

Restrictions, deviations or notes on usage: see *Supplement of Certificate* on p.2.

¹⁾ For details see *Supplement of Certificate* on p.2.

The certificate includes the following information:

- technical data of the power generating unit, the auxiliary equipment used and the software version used;
- schematic structure of the power generating units;
- summarized information on the properties of the power generating unit.

The certificate is comprised of 77 pages (including Annex of 75 pages).

BV project number : 19TH0183
Certificate no. : 21-0004_0
Issued : 2021-03-18
Certification scheme : NSOP-0032-DEU-ZE-V01
Valid until : 2026-01-11

Certification body



Holger Schaffer



Certification body of Bureau Veritas Consumer Products Services Germany GmbH accredited according to DIN EN ISO/IEC 17065
 A partial representation of the certificate requires the written approval of Bureau Veritas Consumer Products Services Germany GmbH

Supplement of Certificate (21-0004_0)

Note:

- ¹⁾ The P_{Emax} is the highest 10-min mean of the active power of a power generating unit defined according to VDE-AR-N 4110:2018 [1]. The P_{600} is the maximum active power peak of the overall system (averaging period 10 min) defined according to FGW TR 3 Rev. 25 [3].

The stated values on the front page of this certificate were determined according to test 4.1.1, FGW TR 3 Rev. 25 [3].

The active power results of the REFUsol 60K-3T can be applied to the REFUsol 50K-3T scaled (by the factor $P_{n, REFUsol 50K-3T} / P_{n, REFUsol 60K-3T} = 0,833$).

Restrictions, deviations or notes on usage:

- The PGUs in the series do not provide test terminals for on-site testing. For necessary on-site testing, a separate test terminal must be installed additionally.
- The on the PGU level implemented Q(U) control function deviates from requirements according to VDE-AR-N 4110:2018-11. This needs to be considered for project planning. If needed, this has to be implemented on the plant level e.g. in the superimposed PGS controller.
- The PGUs in the series provide only one kind of Q(U) control function. The on the PGU level implanted Q(U) control function can be used as *reactive power with voltage limitation function* by suitable setting of the characteristic curve. But this also deviates from requirements according to VDE-AR-N 4110:2018-11. This needs to be considered for project planning. If needed, this has to be implemented on the plant level e.g. in the superimposed PGS controller.
- No Q(P) control function implemented on the unit level. Instead, the $\cos\phi(P)$ control function implemented in the software. This needs to be considered for project planning. If needed, this has to be implemented on the plant level e.g. in the superimposed PGS controller.
- The minimum setting step size of the displacement factor $\cos\phi$ implemented on the PGU level is 0,01, to fulfil the requirement and if needed this has to be implemented on the plant level e.g. in the superimposed PGS controller.
- The default configuration of the units may not meet the reactive power requirement at the grid connection point (see p.45). A permanent active power reduction may be needed. This needs to be considered for project planning.
- The setting range of the stabilisation time of the automatic reconnection does not meet the requirement (adjustable between 0 and 600 s). If needed, this has to be implemented on PGS level via an external interface protection relay.
- In addition to the PGU integrated protection function a fault ride-through tripping curve function is implemented additionally in the software. This function defines a curve exceeding which the unit disconnects from the grid. This needs to be considered for parameterization of the protection relay. The defined self-protection setting of the PGU needs to be considered for parameterization of the protection relay.
- Note to simulation model:
 - The reactive power control functions implemented on the simulation model were not validated directly.
 - The active power control implemented in the simulation model is suitable for application of set point accuracy. The active power gradient is not implemented in the simulation model.
 - An apparent power /current limitation is not implemented in the model. The PQ characteristic curve of the model is not validated.

These need to be considered on the project level.

The certificate is comprised of 77 pages (including Annex of 75 pages).

BV project number : 19TH0183

Certificate no. : 21-0004_0

Issued : 2021-03-18

Certification scheme : NSOP-0032-DEU-ZE-V01

Valid until : 2026-01-11

Certification body

Holger Schaffer



Certification body of Bureau Veritas Consumer Products Services Germany GmbH accredited according to DIN EN ISO/IEC 17065
A partial representation of the certificate requires the written approval of Bureau Veritas Consumer Products Services Germany GmbH